



DATE	REV	DESCRIPTION	AUTH	CHK
4/24/2024	-	INITIAL DRAWING	FP	FP



- NOTES:**
- DIMENSIONS SHOWN ARE NOMINAL AND ARE SUBJECT TO FABRICATION TOLERANCES.
  - EXTERNAL PIPING MUST BE INDEPENDENTLY SUPPORTED.
  - PIPING AND BULKHEAD FITTING MATERIAL IS PVC UNLESS OTHERWISE NOTED.
  - HARDWARE MATERIAL IS TYPE 304 STAINLESS STEEL.
  - MAXIMUM INLET WATER TEMPERATURE IS 140°F. (CONSULT FACTORY FOR HIGHER TEMPERATURE APPLICATIONS).
  - ALL DIMENSIONS ARE IN INCHES.
  - ALL WEIGHTS ARE IN POUNDS. DRY WEIGHT INCLUDES; FAN ASSEMBLY AND TOWER COMPLETE / OPERATING WEIGHT INCLUDES A FULL SUMP.
  - TOWER MOUNTING OPTION #1 - CONCRETE PAD - ENTIRE TOWER BASIN BOTTOM SURFACE TO BE FULLY SUPPORTED BY AN APPROPRIATELY SIZED CONCRETE PAD.
  - TOWER MOUNTING OPTION #2 - BEAM SUPPORTED VIA I-BEAM POCKETS - \* SUPPORT BEAMS AND ANCHOR BOLTS ARE TO BE FURNISHED BY OTHERS. \* BEAMS SHOULD HAVE A MINIMUM TOP FLANGE WIDTH OF 8" 9 8"X31# RECOMMENDED) AND BE IN ACCORDANCE WITH ACCEPTABLE STRUCTURAL DESIGN PRACTICES. THESE BEAMS SHOULD BE LOCATED IN THE INTEGRALLY MOLDED I-BEAM POCKETS AND SHOULD OVER-RUN THE LENGTH OF THE TOWER. \*DO NOT WELD OR BOLT DOWN BEAMS PRIOR TO SETTING THE COOLING TOWER SUMP(S).
  - FINAL YARD PIPING TO AND FROM THE TOWER SHOULD BE FABRICATED FOLLOWING INSTALLATION OF THE TOWERS ONSITE. DUE TO MANUFACTURING AND INSTALLATION TOLERANCES, PREFABRICATION OF EXTERNAL PIPING IS NOT RECOMMENDED.
  - SEE DRAWING DCT-TMX\_2C-SSD-001-1 FOR PLAN VIEW AND SIDE VIEW.

ITEM	QTY	DESCRIPTION	MATERIAL	REMARKS
15	2	FLOAT VALVE	POLYPROPYLENE	NOT SHOWN
14	8	ANCHOR LUGS	ALUMINUM	LOCATION TBD
13	2	VORTEX BREAKER	PVC	NOT SHOWN
12	2	OUTLET STRAINER	PVC COATED	NOT SHOWN
11	28	LOUVER PANEL	PVC	
10	4	FILL MEDIA	PVC	NOT SHOWN
9	4	FILL SUPPORT	FRP	NOT SHOWN
8	4	MIST ELIMINATOR	PVC	NOT SHOWN
7	2	WATER DISTRIBUTION SYSTEM	PVC	
6	4	VELOCITY RECOVERY STACK	POLYETHYLENE	WITH SCREEN
5	4	PROPELLER	FRP/POLYPRO.	
4	4	ELECTRICAL CONNECTION	ALUMINUM	
3	4	MOTOR	ALUM. / STEEL	TEAO, 900 RPM
2	4	FAN RING	COATED STEEL	
1	2	TOWER SHELL	POLYETHYLENE	

**DELTA COOLING TOWERS INC.**  
 185 US HIGHWAY 206 ROXBURY TOWNSHIP, NJ 07836  
 PH: 973-586-2201 FAX: 973-586-2243

**2 CELL TMX SALES ASSEMBLY**

DESIGN CONDITIONS:  
 FLOW RATE TBD GPM  
 INLET TEMP TBD °F  
 OUTLET TEMP TBD °F  
 WET BULB TBD °F  
 ELECTRICAL TBD

INFORMATION CONTAINED HEREIN IS SUBJECT TO CHANGE WITHOUT NOTICE IN THE INTEREST OF PRODUCT IMPROVEMENT.

SCALE 11/16"=1'  
 DATE 5/7/2024

DCT-TMX\_2C-SSD-001-2

OPER. WT. (FULL SUMP)	SEE MODEL
29,520 LBS	15,840 LBS
20,520 LBS	1,152 GALLONS

ITEM	QTY	DESCRIPTION	MATERIAL	REMARKS
15	2	FLOAT VALVE	POLYPROPYLENE	NOT SHOWN
14	8	ANCHOR LUGS	ALUMINUM	LOCATION TBD
13	2	VORTEX BREAKER	PVC	NOT SHOWN
12	2	OUTLET STRAINER	PVC COATED	NOT SHOWN
11	28	LOUVER PANEL	PVC	
10	4	FILL MEDIA	PVC	NOT SHOWN
9	4	FILL SUPPORT	FRP	NOT SHOWN
8	4	MIST ELIMINATOR	PVC	NOT SHOWN
7	2	WATER DISTRIBUTION SYSTEM	PVC	
6	4	VELOCITY RECOVERY STACK	POLYETHYLENE	WITH SCREEN
5	4	PROPELLER	FRP/POLYPRO.	
4	4	ELECTRICAL CONNECTION	ALUMINUM	
3	4	MOTOR	ALUM. / STEEL	TEAO, 900 RPM
2	4	FAN RING	COATED STEEL	
1	2	TOWER SHELL	POLYETHYLENE	