



DATE	REV	DESCRIPTION	AUTH	CHK
2/28/2024	-	INITIAL DRAWING	FP	FP
9/24/2025	A	ADDED DIMENSIONS / DETAIL	FP	FP

- NOTES:
- DIMENSIONS SHOWN ARE NOMINAL AND ARE SUBJECT TO FABRICATION TOLERANCES.
 - EXTERNAL PIPING MUST BE INDEPENDENTLY SUPPORTED.
 - PIPING AND BULKHEAD FITTING MATERIAL IS PVC UNLESS OTHERWISE NOTED.
 - HARDWARE MATERIAL IS TYPE 304 STAINLESS STEEL.
 - MAXIMUM INLET WATER TEMPERATURE IS 140°F. (CONSULT FACTORY FOR HIGHER TEMPERATURE APPLICATIONS).
 - ALL DIMENSIONS ARE IN INCHES.
 - ALL WEIGHTS ARE IN POUNDS. DRY WEIGHT INCLUDES; FAN ASSEMBLY AND TOWER COMPLETE / OPERATING WEIGHT INCLUDES A FULL SUMP.
 - TOWER MOUNTING OPTION #1 - CONCRETE PAD - ENTIRE TOWER BASIN BOTTOM SURFACE TO BE FULLY SUPPORTED BY AN APPROPRIATELY SIZED CONCRETE PAD.
 - TOWER MOUNTING OPTION #2 - BEAM SUPPORTED VIA I-BEAM POCKETS - * SUPPORT BEAMS AND ANCHOR BOLTS ARE TO BE FURNISHED BY OTHERS. * BEAMS SHOULD HAVE A MINIMUM TOP FLANGE WIDTH OF 8" (8"X31# RECOMMENDED) AND BE IN ACCORDANCE WITH ACCEPTABLE STRUCTURAL DESIGN PRACTICES. THESE BEAMS SHOULD BE LOCATED IN THE INTEGRALLY MOLDED I-BEAM POCKETS AND SHOULD OVER-FUN THE LENGTH OF THE TOWER.
 - IF SELECTING TOWER MOUNTING OPTION #2, DO NOT WELD OR BOLT DOWN I-BEAMS PRIOR TO SETTING THE COOLING TOWER SUMP(S)
 - FINAL YARD PIPING TO AND FROM THE TOWER SHOULD BE FABRICATED FOLLOWING TOLERANCES, PREFABRICATION OF EXTERNAL PIPING IS NOT RECOMMENDED.
 - SEE DRAWING DCT-TMX_3C-SSD-001-1 FOR PLAN AND SIDE VIEW.

18	3	EQUALIZER CONNECTION	PVC	4" FNPT
17	3	DRAIN CONNECTION	PVC	2" FNPT
16	3	OVERFLOW CONNECTION	PVC	2" FNPT
15	3	MAKE-UP CONNECTION	PVC	1" FNPT
14	3	WATER OUTLET CONNECTION	PVC	10" FLANGED
13	3	WATER INLET CONNECTION	PVC	8" FLANGED
12	10	TOP CONNECTOR BRACKETS	ALUMINUM	
11	12	LIFTING LUGS	ALUMINUM	
10	12	ANCHOR LUGS	ALUMINUM	SEE NOTE #8 & #9
9	66	LOUVER PANELS	PVC	
8	6	VELOCITY RECOVERY STACK	POLYETHYLENE	WITH SCREEN
7	6	PROPELLER	FRP/POLYPRO	
6	6	ELECTRICAL CONNECTION	ALUMINUM	INISDE FAN ASSEMBLY
5	6	MOTOR	ALUM/STEEL	TEAO, 900 RPM
4	6	FAN RING	COATED CS	
3	30	LOUVER FRAMES	POLYETHYLENE	
2	3	SUMP	POLYETHYLENE	
1	3	UPPER HOUSING	POLYETHYLENE	
ITEM	QTY	DESCRIPTION	MATERIAL	REMARKS

BILL OF MATERIALS			
DESIGN CONDITIONS			
FLOW RATE	TBD	GPM	
INLET TEMP	TBD	°F	
OUTLET TEMP	TBD	°F	
WET BULB	TBD	°F	
ELECTRICAL	TBD		
INFORMATION CONTAINED HEREIN IS SUBJECT TO CHANGE WITHOUT NOTICE IN THE INTEREST OF PRODUCT IMPROVEMENT.			
SCALE 1 1/16" = 1'		DATE 2/28/2024	
SIZE D		DWG NO DCT-TMX_3C-SSD-001-2	REV A

TOTAL HP	18/30/45/60/90/120/150
DRY WT.	23,760 LBS
OPER. WT. (FULL SUMP)	44,280 LBS
OPER. WT. (B OUTLET)	30,780 LBS
SUMP CAPACITY	1,728 GALLONS



DELTA COOLING TOWERS INC.
185 US HIGHWAY 206 ROXBURY TOWNSHIP, NJ 07836
PH: 973-586-2201 FAX: 973-586-2243

TITLE 3 CELL TMX SALES ASSEMBLY

TMX SERIES JOB # TBD

DRAWN BY: Frank Pyszchacki

CHECKED BY: Frank Pyszchacki